NEMO
TILE + STONE

HANDWRITTEN



HANDWRITTEN



HANDWRITTEN



HANDWRITTEN

SIZES

3X6, 3X12

FINISH

GLOSS

V3 MODERATE VARIATION

COLORS

UNSCRIPTED

PEN PAL

PAR AVION



PRIVATE AFFAIR



POST CARD

GOLD LEAF



LOVE LETTER



DEAR SIR



INKWELL

UNSCRIPTED

PEN PAL

PAR AVION

UNSCRIPTED

PEN PAL

PAR AVION



PRIVATE AFFAIRS



POST CARD

GOLD LEAF



PRIVATE AFFAIRS



POST CARD

GOLD LEAF



LOVE LETTER



DEAR SIR



INKWELL



LOVE LETTER



DEAR SIR



INKWELL

HANDWRITTEN


MOSAICS

UNSCRIPTED - LEAF MOSAIC

PEN PAL - LEAF MOSAIC



PAR AVION - LEAF MOSAIC




PRIVATE AFFAIR - LEAF MOSAIC




POST CARD - LEAF MOSAIC

GOLD LEAF - LEAF MOSAIC



LOVE LETTER - LEAF MOSAIC



DEAR SIR - LEAF MOSAIC



INKWELL - LEAF MOSAIC

UNSCRIPTED - DIAMOND MOSAIC

PEN PAL - DIAMOND MOSAIC



PAR AVION - DIAMOND MOSAIC



PRIVATE AFFAIR - DIAMOND MOSAIC



POST CARD - DIAMOND MOSAIC


GOLD LEAF - DIAMOND MOSAIC



LOVE LETTER - DIAMOND MOSAIC



DEAR SIR - DIAMOND MOSAIC



INKWELL - DIAMOND MOSAIC


HANDWRITTEN

HANDWRITTEN

Sizes & Finishes

Field Tile

Nominal (in)	Thickness (in	Finish
3 x 6	3/8	Gloss
3 x 12	3/8	Gloss
3 x 6 Picket	3/8	Gloss
3 x 6 Gothic Picket	3/8	Gloss

Crossville recommends a 1/8 to 1/4 inch grout joint.

Mosaics

Nominal (in)	Thickness (in)	Finish
Diamond Mosaic	3/8	Gloss
Leaf Mosaic	3/8	Gloss

Mesh mounted on a 12 x 12 sheet.

Coordinating Trim


Nominal (in)	Thickness (in)	Finish
1/2 x 6 Arrow Liner	5/8	Gloss
1/2 x 6 Dome Liner	5/8	Gloss
2-1/2 x 6 Chair Rail	3/4	Gloss
3 x 6 Bullnose	3/8	Gloss
3 x 3 Bullnose Corner	3/8	Gloss



3 x 3 Bullnose Corner | 3 x 6 Bullnose | 2-1/2 x 6 Chair Rail | 1/2 x 6 Dome Liner | 1/2 x 6 Arrow Liner

Shade & Texture Index

Handwritten has a shade variation of V3.



V1 Uniform appearance
V2 Slight Variation
V3 Moderate Variation
V4 Substantial Variation

This tile product is produced with a V3 variation. Expect that the amount of color and texture on each piece may vary significantly. Inspect the product upon delivery and for best results, blend tile from several cartons during installation.



NEMO
TILE + STONE

HANDWRITTEN